

OFFICE OF THE PROJECT DIRECTOR
LADAKH RENEWABLE ENERGY DEVELOPMENT AGENCY(LREDA), LEH
CORRIGENDUM-II

The following corrigendum should be read for NIT No.26 “Rate Contract for Design, Manufacture, Supply, and Installation of **Evacuated Tube Collector** Based Solar Water Heaters at Various Sites in Leh District of Jammu and Kashmir”.

1. **Section I (A).8 shall be read as** “Scope of work for the bidder is upto erection of the system only. Beneficiary is responsible for all other works necessary of commissioning. However the bidder should provide the beneficiary with technical assistance or a booklet containing diagrammatic details for further installation stages.
Payment to the bidder shall be made after erection of the system a certificate for which should be signed by the beneficiary.”
2. **Section I (A).8 (d) shall be read as** “Consumables such as sacrificial anode, electrical back up heater, rubber grommets, tube end caps, washer , nuts and bolts are not included in the warranty, however the bidder should have enough spare parts in their store.”
3. **Section I (A).9 shall be read as:** “5% of payment shall be released in five equal installments at the end of each year on submission of documentary evidence confirming successful O&M during that year OR upon submission of a bank guarantee for an equal amount for a period.”
1. **Annexure I (Technical Specifications). 1 shall be read as:** Following evacuated tube shall also be eligible for supply:
Outer Diameter: 47 mm dia
Inner Diameter: 37 mm dia
Length : 1500 mm
Triple layered 1.6mm thick borosilicate glass
Minimum 15 per 100 LPD System
2. **Annexure I (Technical Specification). 2 shall be read as**
“Pure polyester pre-coated 0.5 mm thick GI sheet can also be used for outer cladding.”
3. **Annexure I (Technical Specification).3 shall be read as**
“The backup heater should be provided with an Auto thermostat where the beneficiary can set the temperature from 35 to 70 degree centigrade of heating.”

Project Director
LREDA-LAHDC
Leh

Project Director
LREDA-LAHDC
Leh-Ladakh